



Air Handling Units & Heat Recovery NRG 0, 1 & 2

1.1. General

A. Provide a heat recovery air handling unit to meet the performance and configuration as indicated in the schedule and detail drawings. The heat recovery air handling unit shall be tested to BS848 Part 1 and shall be of the Ecovent NRG type as manufactured by VES Andover Ltd a company accredited with BS EN ISO 9001:2008.

1.2. Unit Construction

A. The unit shall be provided pre-assembled comprising of a rigidly constructed single skinned galvanised sheet steel case, supply & extract centrifugal backward curved fans with direct drive motor, supply and extract G4 pleated panel filters, and plastic plate heat exchanger incorporating drain pan.

B. The size 1 & 2 units shall be available with optional fitted electric or hot water heating as indicated in the schedule & detail drawings.

C. The size 1 & 2 units shall be available in plantroom or weatherproof construction as indicated in the schedule and detail drawings.

D. The size 1 & 2 units shall be fitted with a heat exchanger bypass duct, incorporating a bypass damper to allow free summer cooling.

E. The unit shall have circular 'safe fit' duct spigots complete with rubber gasket seals as indicated in the schedule and detail drawings.

F. The unit casework shall incorporate high quality leak resistant gaskets on service doors and panels.

G. The casework shall be fitted with an inert flame retardant acoustic lining as standard to ensure maximum thermal insulation and reduced noise transmission.

H. Access for maintenance shall be via a removable lid, allowing access for the cleaning or removal of internal components as indicated in the detail drawings.

I. The casework shall incorporate mounting brackets compatible with drop-rod systems.

J. The unit shall be compatible with optional self-levelling feet as provided by VES Andover Ltd.

K. Plantroom unit casework & spigots shall be supplied naturally finished in high quality galvanised steel as standard. Optional powdercoat colour as indicated in the schedule.

L. Weatherproof units shall be supplied powdercoated signal grey RAL7004 as standard. Colour according to schedule.

M. The unit shall be designed to be secured to a suitable base, wall or ceiling, ensuring the use of correct fixings for the application and taking into account individual unit weight as indicated in the schedule and detail drawings.

N. The size 0 unit shall be suitable for on-site handling & access modifications as indicated in the detail drawings and O&M documentation.

O. The size 1 & size 2 units shall be supplied with access & handling as indicated in the schedule & detail drawings.



1.3. Fans

- A. The fan impellers shall be galvanised steel, backward curved blade construction.
- B. The impellers shall be statically and dynamically balanced to G 2.5 / G 6.3 according to ISO1940 part 1.
- C. The fan impellers shall be mated with aerodynamic bell inlet eyes for high efficiency and low noise generation.
- D. The fan impellers are supplied as standard in natural uncoated finish. Acrythane coating shall be available as indicated in the schedule.

1.4. Motors

- A. The fans shall incorporate external rotor motors to insulation class F, IP44 environmental protection rating & shall be supplied with thermal protection cut-out as standard.
- B. The integrated motor shall be supplied epoxy painted grey to RAL7032

1.5. Plate Heat Exchanger

- A. The unit shall be supplied with an ECA approved full PVC plate heat exchanger with a minimum efficiency of 50%
- B. The plate heat exchanger shall incorporate a 100% recycled exchange matrix and heavy gauge PVC framework as standard.
- C. The plate heat exchanger matrix shall be aerodynamically designed, with built-in spacers ensuring a constant plate separation.
- D. The plate heat exchanger shall be available with optional virgin plastic exchange matrix for corrosive environments as indicated in the schedule.

1.6. Drain Pan

- A. The unit shall include a built-in condensate drain pan as standard.
- B. The drain pan shall be situated on the extract air off side of the Heat Exchanger as standard.
- C. The size 0 units shall have an on-site adjustable drain pan position to suit specification.
- D. The drain pan shall be designed with a fluid sump compatible with an optional peristaltic pump as supplied by VES Andover Ltd.
- E. The drain pan shall be manufactured in vacuum formed plastic & finished black.

1.7. Filtration

- A. The filters shall be 37mm pleated filter media as standard, with rigid wax treated cardboard moisture resistant frame.
- B. Filters shall be to BS EN 779 Classification Grade G4 as standard, grade as indicated in the schedule and detail drawings.



1.8. Heater Battery

A. The size 1 & 2 units shall be available with hot water or electric element heating as indicated in the schedule and detail drawings.

B. The hot water heater battery shall be of copper tube, aluminium fin block construction, with galvanised sheet steel casework. The flow & return pipe connections shall be handed as indicated in the schedule and detail drawings.

C. The hot water heater battery shall be available with alternative fin coatings by special order, as indicated in the schedule.

D. The electric heater battery shall be suitable for single or three phase supply with thyristor or stepped control as indicated in the schedule and detail drawings.

E. The electric heater battery shall consist of an element array sized to suit the steps and phases as indicated in the schedule and detail drawings. The elements shall consist of a tubular incolloy shroud containing compressed magnesium oxide powder packed around a Nickel Chromium resistance wire. The element array shall be evenly spread across the open area of the duct.

F. Where multiple elements are required to achieve the steps and phases as indicated in the schedule, elements shall be linked by copper busbar or terminated with electrical connectors.

G. The electric heater battery shall be fitted as standard with a 130°C non-adjustable thermal safety cutout, with manual reset.

H. All electric heaters shall be 1500V flash tested, and resistance tested for correct component assembly. Test certificates shall be available on request.

1.9. Operation Environment

A. The unit shall be designed to operate in ambient temperatures from -20°C up to 40°C, and can run continuously at up to 80% humidity level.

B. The fan impellers shall be available with optional Acrythane finish suitable for coastal or corrosive environments.

2.0. Controls

A. The unit shall be fitted as standard with a dual fan speed control system with max/min speed & 0-10v BMS control, i.e Air Quality or Temperature sensor.

B. The unit shall be available with optional remote mounted CPC control panel as manufactured by VES Andover Ltd. to suit electric or hot water heating.

C. The size 1 & 2 units shall be suitable for fitted control panels as manufactured by VES Andover Ltd.

C. Fitted Controls shall be positioned as indicated in the schedule & detail drawings.

D. Controls shall be supplied with internally mounted circuit breakers, run, trip & panel live indication & lockable door isolation switch.

E. Control panels shall have individual circuit breakers for Supply, Extract, Control & Electric Heater Battery where indicated in the schedule & detail drawings.



F. Fitted controls shall be supplied with a supply air duct sensor & 10m of cable, to be fitted on-site by others as indicated in the schedule.

G. Fitted controls shall be supplied with a wired touch screen remote controller.

H. Fitted controls shall be fully pre-wired to internal components. Hot water controls shall be pre wired to optional four port valve & optional frost stat supplied by VES Andover LTD as indicated in the schedule.

2.1 Ancillaries

A. The unit shall be fully compatible with a standard range of spigot mounted silencers. The silencers shall be suitable for direct mounting to the unit.

B. The silencer shall be a rigidly constructed single skinned galvanised sheet steel case lining incorporating internal splitting vanes lined with resin bonded mineral wool.

C. The silencer casework shall be provided naturally finished in high quality galvanised steel as standard. Internal & External powder coat available as indicated in the schedule. Colour to be in accordance with schedule.

Download specification from www.ves.co.uk/information-centre